




## Natural Water Purifier “Plus” Option

1. When a pool has a capacity of 22,000 gallons (18,000 gallons for a Model 1500) or more, a second ionization chamber must be installed. If the ambient temperature is quite high, or the pool will be constantly heated or the pool will experience a heavy bather load it may be advisable to install the “Plus Option” on a pool 20,000 gallons (16,000 gallons for a Model 1500) or greater.
2. Please refer to the diagram on page 2. The suggested installation is based on practical results on hundreds of installations.

Please note the chambers are installed on a horizontal (parallel to the ground) run of pipe. The plumbing “T”s that accomplish the splitting and gathering of the water have the riser parallel to the ground. As usual the riser of the ionization chamber points downward.

The manifold formed by the chambers, “Ion T’s”, and 90° pieces must be level. This will help insure that the water evenly splits in half.

3. The electrical hookup is accomplished with the factory supplied cord when the “Plus Option” is ordered. The chambers are wired in parallel. If the factory cord is not used , at least 18 awg wire must be used for interconnection of the chambers.
4. Refer to the diagram on the next page



PLUS OPTION